TUMKUR DIVISION.

Dated 25th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 26th August 1918, for building four blocks of cows' sheds and a shed for calves with a spare room in the Kunigal Stud Farm. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on all days, except Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

4. Each tender must be accompanied by a deposit of rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Building four blocks of cows' sheds and a shed for calves with a spare room in the Kunigal Stud Farm," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract quantity for building four blocks of cows' sheds and a shed for calves with a spare room in the Kunigal Stud Farm.

No.	Items of work	Per	Quantity
	Constructing four blocks of cows-sheds for 80 cows. (details for a block for 20 cows.)		
1	Earthwork excavation	C. yd.	88
2	Stone concrete in chunam	C. ft.	576
3	Burnt stone pillars, 6" thick and 1 foot broad, including dressing, cutting grove and firing, etc.	S. ft.	806
4	Flagging with burnt stone slabs over 6" gravel and cement pointing	Sq.	13'90
5	Burnt stone slabs, 3" thick	S. ft.	552
6	Do do 6" thick	"	96
7	Dressing burnt stone slabs, including rounding at top	"	296
8	Honney wood work, including wood oiling	C. ft.	124'00
9	Roofing with 1st class Mangalore tiles, over teakwood reepers, etc., complete.	Sq.	21'29
10	Ridge tiles set in mortar	R. ft.	53
11	Dwarf walls over gable ends	"	72
12	Constructing V-shaped drain, including cement plastering	"	100
13	Burnt stone slabs with iron rings	Each.	20
14	Levelling ground and removing roots, etc.	Lump	sum.
	Constructing calves' shed.		
1	Earthwork excavation	C. yd.	28
2	Burnt stone in clay	C. ft.	1,193
3	Burnt brick in clay	"	1,517
4	Chunam plastering	Sq.	28'86
5	Burnt stone slabs, roughly dressed, including cutting holes	S. ft.	54
6	Honney wood work wrought and put up	C. ft.	134'25
7	Honney wood battened doors	S. ft.	46
8	Do do windows...	"	16
9	Teakwood gate	"	16
10	Chocolate painting	Sq.	2'69
11	Burnt stone slabs, roughly dressed	S. ft.	72
12	Flooring with clinched bricks with cement pointing on 3" concrete	Sq.	7'32
13	Cuddappah slab flooring over 3" concrete bed and cement pointing	"	3'00
14	Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	"	17'54
15	Ridge tiles set in mortar	R. ft.	76
16	Chunam pointing	Sq.	2'74
17	Chunam borders	R. ft.	48
18	White and colourwashing	Sq.	28'86
19	Levelling ground and removing rubbish, etc.	Lump	sum.

Dated 30th July 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 26th August 1918, for constructing a combined building for Sub-Registrar's Office and Bonded Warehouse at Maddagiri. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 12 [illegible]

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (150) one hundred and fifty only in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a combined building for Sub-Registrar's Office and Bonded Warehouse at Maddagiri," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	54
2	Burnt stone in clay	C. ft.	1913
3	Burnt brick in clay	"	2,605
4	Burnt stone slabs, one line, dressed	S. ft.	590
5	Plastering with chunam	Sq.	60·50
6	Chunam pointing	"	8·45
7	White and colourwashing	"	60·50
8	Teakwood work with wood oiling	C. ft.	165·50
9	Roofing with 1st class Mangalore tiles with teak reepers	Sq.	17·60
10	Ridge tiles set in mortar	R. ft.	52
11	Cuddam borders	"	143
12	Terrace roofing	Sq.	6·07
13	Cornice, 9" thick	R. ft.	257
14	Cutting channels in the corbel and stone pillars for bressumers to rest	Each	28
15	Teakwood ornamental eave boards	R. ft.	113
16	Parapet wall over terrace	"	113
17	Teakwood panelled doors, including fastenings, etc., complete	S. ft.	114
18	Teakwood panelled doors with four-folded shutters with fastenings, etc., complete.	"	44
19	Iron clamps for doors at 4, and windows at 2, each	No.	56
20	Teakwood windows inside glazed and outside panelled shutters with ¼" iron bars, iron fastenings, etc., complete.	S. ft.	157
21	Teakwood glazed ventilators with expanded metal shutters and iron clamps, etc., complete.	"	21
22	Teak finials	Each.	2
23	Teak terminals	"	4
24	Silicate painting	Sq.	10·60
25	Flooring with Cuddappah slabs, over 3" concrete and cement pointing	"	13·60
26	Flooring with granite slab, over 3" to 4" sandbed and cement pointing, etc.	"	3·64
27	Expanded metal partition with four-folded shutters with teak frames and painting, etc., complete.	S. ft.	186
28	Teakwood screen with double shutters, including iron work and painting, etc., complete.	"	72
29	Burnt brick in chunam	C. ft.	502
30	Clearing site and levelling ground, tarring portion of wood work in walls and forming ramp in the side of verandah of spirit room.	Lump sum	
31	Zinc rain water down pipe	R. ft.	112
32	Teakwood windows, inside glazed shutter outside expanded metal fixed with iron bars or fastenings, etc., complete.	S. ft.	95

N. G. KRISHNA IYENGAR,
Executive Engineer.

HASSAN DIVISION.

Abstract Notification.

The attention of the public is invited to the Notification dated 27th July 1918, published in page 722 of Part IV of 32nd issue of *Mysore Gazette*, wherein tenders for constructing a combined building for the Sub-Registrar's Office and Bonded Warehouse at Hole-Narsipur.

R. W. SCALDWELL,
Executive Engineer.

KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published in *Mysore Gazette*, dated 1st August 1918, on page 701, Part IV, calling for tenders for reconstructing the Fort anikat across Yagachi river.

K. PONNAPPA,